

Optional Parts for Geberit Duofix Carrier 111.490.00.1

Product Specifications

Installation accessories for concealed carrier for wall-hung lavatories. Accessories shall be for alternate frame installation and connection sets between carrier and lavatory fixture.

Warranty








One-year warranty against manufacturers' defect.

Features

Installation accessories for:

- Pre-wall installation
- Corner installation
- Post-tension concrete floors
- Non-standard stud distances
- Alternate bolts caps
- Finished wall thicknesses to 7.09" (18 cm)


Mounting Accessories for Carrier Frames

Description	Model No.
 Frame to wall anchoring for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall	111.815.00.1
 Frame to wall anchoring for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall corner installations	111.835.00.1
 Frame to wall anchoring where foot installations into floor are not allowed for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall	111.867.00.1
 Fastening set for sinks with 14.9"-22.8" (38-58 cm) mounting centers	111.868.00.1
 Frame to stud fastening set for extended stud spacing from 19.75"-25.56" (50-65 cm)	111.869.00.1
 Frame to wall anchoring extensions for 7.87"-15.75" (20-40 cm) thick unfinished pre-wall	111.887.00.1
 Elbow supply fitting set, Gun Metal	465.034.00.1

Lavatory Connection Accessories

 Cover caps with leveling washer, Plastic, Alpine White	217.713.11.1
--	--------------

Required Accessories for 3.50"-7.00" (9-18 cm) Finished Wall Thickness

 Mounting rod M10 x 10" long. Not supplied.	—
--	---



ARCHITECT/ENGINEER APPROVAL

Job Name _____

Date _____ Quantity _____

Model Specified _____

Variations Specified _____

Customer/Wholesaler _____

Contractor _____

Architect _____

Geberit
2100 S. Clearwater Drive
Des Plaines, IL 60018
USA

P 800-566-2100
F 847-803-5454

→ geberit.us